Bid Tabulation: Zapata County Airport

Project ID	NTB2521ZAPAT00053	**Bid Opening**	October 14, 2026 1:00 PM
TxDOT CSJ #	2521ZAPAT	**Location**	TxDOT Stassney Campus
Scope	Airfield Pavement and Electrical Improvements	**Bidders**	3
Description	Zapata County Airport (APY) Airfield Pavement and Electrical Improvements	**Low Bidder**	**Anderson Columbia Company, Inc. ($5,660,055.00)**

Item	Qty	Unit	Description	Anderson Columbia Company, Inc. LOW BIDDER		Sterling Delaware Holding Company		Foremost Paving, Inc.	
				Unit Price	Total	Unit Price	Total	Unit Price	Total
C-105	1	LS	CONTRACTOR MOBILIZATION (8%)	$320,000.00	$320,000.00	$500,000.00	$500,000.00	$500,000.00	$500,000.00
C-100	1	LS	CONTRACTOR QUALITY CONTROL PROGRAM	$152,000.00	$152,000.00	$150,000.00	$150,000.00	$180,000.00	$180,000.00
C-102-5.1a	1	LS	TEMPORARY AIR AND WATER POLLUTION, SOIL EROSION, AND SILTATION CONTROL	$100,000.00	$100,000.00	$98,000.00	$98,000.00	$94,435.00	$94,435.00
P-140-3.1	1	LS	TEMPORARY BARRICADES AND MARKING FOR PAVEMENT CLOSURE	$18,000.00	$18,000.00	$6,800.00	$6,800.00	$151,795.20	$151,795.20
P-101-5.1	44,600	SY	PAVEMENT REMOVAL AND STOCKPILE	$5.20	$231,920.00	$1.22	$54,412.00	$9.85	$439,310.00
P-152-4.1	15	CY	DRAINAGE EXCAVATION AND TRENCHING	$44.00	$660.00	$100.00	$1,500.00	$38.50	$577.50
P-152-4.4	60,410	SY	EXCAVATION, GRADING, AND SUBGRADE PREPARATION	$1.70	$102,697.00	$4.70	$283,927.00	$4.36	$263,387.60
P-152-4.2	880	CY	EMBANKMENT IN PLACE	$16.00	$14,080.00	$20.00	$17,600.00	$46.94	$41,307.20
P-152-4.5	51,550	SY	GRADING IN UNPAVED AREAS	$0.70	$36,085.00	$3.50	$180,425.00	$1.24	$63,922.00
P-152-4.6	23,620	SY	TOPSOIL REMOVAL AND STOCKPILE (4-5 INCHES) TO REUSE	$0.50	$11,810.00	$0.90	$21,258.00	$1.52	$35,902.40
P-602-5.1	17,680	GAL	EMULSIFIED ASPHALT PRIME COAT (0.3 GAL/ SY)	$6.00	$106,080.00	$6.00	$106,080.00	$9.12	$161,241.60
P-603-5.1	5,900	GAL	EMULSIFIED ASPHALT TACK COAT (0.10 GAL/ SY)	$5.00	$29,500.00	$5.00	$29,500.00	$9.72	$57,348.00
P-620-5.1a	1	LS	SAND BLAST, CLEAN, AND REMARK EXISTING SEGMENTED CIRCLE MARKER SYSTEM, INCLUDING REFLECTIVE MEDIA (BEADS)	$10,000.00	$10,000.00	$1,545.00	$1,545.00	$9,900.00	$9,900.00
P-620-5.2b	42,065	SF	RUNWAY AND TAXIWAY MARKING INCLUDING REFLECTIVE MEDIA (BEADS)	$1.80	$75,717.00	$0.91	$38,279.15	$1.27	$53,422.55
TX-247-6.1	58,930	SY	GRADE 1-2, TYPE A CRUSHED AGGREGATE BASE COURSE (8-INCH THICKNESS)	$32.60	$1,921,118.00	$42.50	$2,504,525.00	$49.66	$2,926,463.80
TX-341	9,770	TON	HOT MIX ASPHALT, TYPE D (3- INCH THICKNESS), PLACED IN TWO 1.5-INCH LIFTS	$126.00	$1,231,020.00	$190.00	$1,856,300.00	$206.42	$2,016,723.40
D-701-5.1	15	LF	EXTEND EXISTING 18-INCH REINFORCED CONCRETE PIPE (RCP), COMPLETE IN PLACE, INCLUDING REMOVAL OF EXISTING	$280.00	$4,200.00	$500.00	$7,500.00	$632.50	$9,487.50
D-752-5.1	1	EA	REPLACE EXISTING CONCRETE- REINFORCED SAFETY END TREATMENT, FOR 18- INCH RCP PIPE, COMPLETE IN PLACE, INCLUDING REMOVAL OF EXISTING	$4,000.00	$4,000.00	$3,800.00	$3,800.00	$5,390.00	$5,390.00
MC1-1	18	EA	FURNISH AND INSTALL AIRCRAFT TIE- DOWN ANCHORS, COMPLETE	$650.00	$11,700.00	$688.89	$12,400.02	$1,430.00	$25,740.00

Item	Qty	Unit	Description	Anderson Columbia Company, Inc. LOW BIDDER		Sterling Delaware Holding Company		Foremost Paving, Inc.	
				Unit Price	Total	Unit Price	Total	Unit Price	Total
T-901-5.1	11	AC	SEEDING, FERTILIZING, AND WATERING, COMPLETE	$6,500.00	$71,500.00	$3,500.00	$38,500.00	$3,726.80	$40,994.80
T-905-5.1	22,700	SY	TOPSOIL , OBTAINED ON SITE, STOCKPILED (4- TO 6-INCH MINIMUM), INCLUDE AMENDMENT, IN PLACE	$1.00	$22,700.00	$1.10	$24,970.00	$1.29	$29,283.00
L-101-5.1	1	LS	FURNISH AND INSTALL 1-801 A(L), LED CLASS 1 ROTATING BEACON INCLUDING REMOVAL OF EXISTING BEACON, IN-PLACE AND ALL ELECTRICAL CONSTRUCTION	$16,000.00	$16,000.00	$29,032.40	$29,032.40	$16,500.00	$16,500.00
L-103-5.1	1	LS	FURNISH AND INSTALL 50-FOOT TIP-DOWN TOWER AND FOUNDATION, INCLUDING REMOVAL OF EXISTING TOWER IN-PLACE AND ALL ELECTRICAL CONSTRUCTION	$67,000.00	$67,000.00	$55,061.44	$55,061.44	$68,200.00	$68,200.00
L-107-5.1	1	EA	FURNISH AND INSTALL LED 1-B INTERNALLY LIGHTED, FAA SIZE 2 WIND CONE AND FOUNDATION ON TILT-OVER MAST, INCLUDING REMOVAL OF EXISTING WIND CONE, FOUNDATION AND ALL ELECTRICAL CONSTRUCTION	$18,000.00	$18,000.00	$16,017.87	$16,017.87	$18,700.00	$18,700.00
L-108-5.1	12,300	LF	TRENCHING, BACKFILL, AND COMPACT FOR PVC CONDUIT, 24-INCH MINIMUM DEPTH	$9.70	$119,310.00	$7.51	$92,373.00	$9.90	$121,770.00
L-108-5.2	660	LF	TRENCHING, BACKFILL, AND COMPACT FOR PVC CONDUIT, 40-INCH MINIMUM DEPTH	$14.00	$9,240.00	$20.02	$13,213.20	$14.30	$9,438.00
L-108-5.3	14,700	LF	NO. 8 AWG 5KV, L-824 TYPE C CABLE, INSTALLED IN TRENCH, DUCT BANK OR CONDUIT, EDGE LIGHTS	$2.70	$39,690.00	$3.50	$51,450.00	$2.75	$40,425.00
L-108-5.4	9,070	LF	NO. 8 AWG SKV, L-824 TYPE C CABLE, INSTALLED IN TRENCH, DUCT BANK, OR CONDUIT, PAPI-2	$2.70	$24,489.00	$3.50	$31,745.00	$2.75	$24,942.50
L-108-5.5	14,470	LF	NO. 6 AWG, SOLID, BARE COPPER GROUND WIRE W/ GROUNDING RODS, INSTALLED ABOVE DUCT BANK OR CONDUIT, INCLUDING CONNECTIONS/TERMINATIONS	$2.70	$39,069.00	$4.51	$65,259.70	$2.75	$39,792.50
L-108-5.6	400	LF	NO. 6 AWG, INSULATED, STRANDED EQUIPMENT BONDING, INSTALLED IN DUCT BANK OR CONDUIT	$2.70	$1,080.00	$5.01	$2,004.00	$2.75	$1,100.00
L-108-5.7	60	LF	INSTALL NO. 4/0 AWG VAULT COUNTERPOISE COMPLETE WITH TRENCH, GROUND RODS, AND EXOTHERMIC BONDING, AROUND NEW VAULT	$20.00	$1,200.00	$50.06	$3,003.60	$20.90	$1,254.00
L-109-7.1	1	EA	FURNISH AND INSTALL NEW 7.5KW, 6.6 AMP, THREE-STEP CONSTANT CURRENT REGULATOR WITH OUTPUT VOLTMETER AND AMMETER, MIRLS	$19,000.00	$19,000.00	$25,027.93	$25,027.93	$19,800.00	$19,800.00
L-109-7.2	1	EA	FURNISH AND INSTALL 2.0KW, 6.6 AMP, THREE-STEP CONSTANT CURRENT REGULATOR WITH OUTPUT VOLTMETER AND AMMETER, PAPI-2	$14,000.00	$14,000.00	$23,025.69	$23,025.69	$13,700.50	$13,700.50
L-109-7.3	1	EA	FURNISH AND INSTALL NEW L-854 RADIO CONTROLLER AND EXTERNAL ANTENNA MOUNTED ON VAULT	$7,000.00	$7,000.00	$7,508.38	$7,508.38	$7,315.00	$7,315.00
L-109-PLANS	1	EA	FURNISH AND INSTALL NEW PHOTOELECTRIC CONTROLLER	$1,800.00	$1,800.00	$5,005.59	$5,005.59	$1,870.00	$1,870.00
L-109-7.4	1	LS	CONSTRUCTION OF 10- X 12-FOOT PREFABRICATED CONCRETE BUILDING AND FOUNDATION IN PLACE	$200,000.00	$200,000.00	$150,167.57	$150,167.57	$19,800.00	$19,800.00

Item	Qty	Unit	Description	Anderson Columbia Company, Inc. LOW BIDDER		Sterling Delaware Holding Company		Foremost Paving, Inc.	
				Unit Price	Total	Unit Price	Total	Unit Price	Total
L-110-5.1	12,300	LF	INSTALL NON-ENCASED ELECTRICAL CONDUIT, 2-INCH SCH 40 PVC, IN TRENCH	$4.50	$55,350.00	$3.00	$36,900.00	$4.68	$57,564.00
L-110-5.2	660	LF	CONCRETE-ENCASED ELECTRICAL CONDUIT DUCT BANK, NEW TWO 2-INCH SCH 40, PVC, IN TRENCH	$32.00	$21,120.00	$30.03	$19,819.80	$33.00	$21,780.00
L-115.1	15	EA	ELECTRICAL HANDHOLE, 12X24 INCHES, L-867B, WITH CONCRETE ENCASEMENT	$2,000.00	$30,000.00	$1,201.34	$18,020.10	$2,200.00	$33,000.00
L-115.2	3	EA	HEAVY-DUTY ELECTRICAL BOX WITH LID, 17X30X24 INCHES, AT VAULT BUILDING	$4,500.00	$13,500.00	$3,003.35	$9,010.05	$4,950.00	$14,850.00
L-125.1	118		REMOVE AND DISPOSE OFF SITE, EXISTING STAKE-MOUNTED RUNWAY EDGE ‘LIGHTS FIXTURES (INCLUDING ALL UNDERGROUND ‘CONDUIT, WIRING CONNECTIONS, AND BOXES), MIRLS	$180.00	$21,240.00	$200.22	$23,625.96	$192.50	$22,715.00
L-125.2	11	EA	REMOVE AND DISPOSE OFF SITE, EXISTING DIRECTIONAL SIGNAGE {INCLUDING ALL UNDERGROUND CONDUIT, WIRING CONNECTIONS, BOXES, AND CONCRETE PADS)	$600.00	$6,600.00	$500.56	$5,506.16	$660.00	$7,260.00
L-125-3	4	EA	REMOVE AND DISPOSE OFF SITE, EXISTING REILS UNITS ON RWY 12-30 END {INCLUDING ALL UNDERGROUND CONDUIT, WIRING CONNECTIONS, BOXES, AND CONCRETE FOUNDATION PADS)	$900.00	$3,600.00	$1,001.12	$4,004.48	$990.00	$3,960.00
L-125-4	45	EA	L-861, INSTALL LED MEDIUM INTENSITY RUNWAY EDGE LIGHTS (WHITE/WHITE, 6-UNITS) AND (YELLOW/WHITE, 39-UNITS), BASE MOUNTED ON CONCRETE-ENCASED CAN	$2,600.00	$117,000.00	$1,501.68	$67,575.60	$2,860.00	$128,700.00
L-125-5	32	EA	INSTALL LED MEDIUM INTENSITY RUNWAY THRESHOLD LIGHTS (RED/RED, 16- UNITS), (BLANK/GREEN, 12-UNITS), AND EDGE LIGHTS (YELLOW/GREEN, 4-UNITS) BASED MOUNTED ON CONCRETE-ENCASED CAN, AS SPECIFIED ON PLANS	$2,600.00	$83,200.00	$1,802.01	$57,664.32	$2,860.00	$91,520.00
L-125-6	10	EA	ONE MODULE, SIZE 1, STYLE 2, INTERNALLY LIGHTED LED GUIDANCE SIGN, BASE MOUNTED ON CONCRETE-ENCASED CAN	$7,000.00	$70,000.00	$4,505.03	$45,050.30	$7,700.00	$77,000.00
L-125-8	1	EA	THREE MODULE, SIZE 1, STYLE 2, INTERNALLY LIGHTED LED GUIDANCE SIGN, BASE MOUNTED ON CONCRETE-ENCASED CAN	$11,000.00	$11,000.00	$6,006.70	$6,006.70	$11,275.00	$11,275.00
L-125-9	2	EA	INSTALL NEW L-881, PAPI-2, STYLE B, LED TILUMINATION, EQUIPPED WITH INTERNAL ADJUSTABLE BAFFLES, MOUNTED ON CONCRETE FOUNDATIONS, COMPLETE, INCLUDING ADJUSTMENTS DURING FAA FLIGHT INSPECTION	$28,000.00	$56,000.00	$35,039.10	$70,078.20	$28,050.00	$56,100.00
L-125-10	139	EA	INSTALL L-853 TAXIWAY REFLECTIVE MARKERS (BLUE 86-UNITS AND GREEN 53-UNITS) AS SPECIFIED ON PLANS, COMPLETE IN PLACE	$20.00	$2,780.00	$19.00	$2,641.00	$165.00	$22,935.00
P-610-6.2	2	EA	PREPARE, INSTALL 100- X 10- FOOT THRESHOLD CONCRETE PAD AROUND L-806 LIGHT BASES, COMPLETE IN PLACE	$31,500.00	$63,000.00	$20,022.35	$40,044.70	$34,430.00	$68,860.00

Item	Qty	Unit	Description	Anderson Columbia Company, Inc. LOW BIDDER		Sterling Delaware Holding Company		Foremost Paving, Inc.	
				Unit Price	Total	Unit Price	Total	Unit Price	Total
P-610-6.3	4	EA	PREPARE, INSTALL 40- X 10-FOOT DISPLACED THRESHOLD CONCRETE PAD AROUND L-806 LIGHT BASES, COMPLETE IN PLACE	$13,500.00	$54,000.00	$8,008.94	$32,035.76	$14,190.00	$56,760.00
			Total Bid		**$5,660,055.00**		**$6,945,199.67**		**$8,185,518.05**
			Base Bid per TxDOT Summary Sheet		$5,660,055.00		$6,945,199.67		$8,185,518.05
			Rank		1		2		3
			Above Low Bid		-		22.7%		44.6%

Bidders are ordered low to high by base bid; the low bidder is shaded green. Unit prices were read from TxDOT's scanned bid tabs and verified: each bidder's line totals reconcile exactly to the base bid on the summary sheet.
Source: https://www.dot.state.tx.us/AVN/avninfo/status/construct/ntb2521zapat00053br1.pdf. Generated October 21, 2026.